


NOTES:


- 1. THE ASSEMBLY SHALL BE INSTALLED WITH MINIMUM HORIZONTAL CLEARANCES OF 30 INCHES FREE FROM OBSTRUCTIONS IN ALL DIRECTIONS.
- 2. GUARD POSTS SHALL BE INSTALLED IF THE ASSEMBLY IS EXPOSED TO POSSIBLE DAMAGE FROM VEHICULAR TRAFFIC, AS DETERMINED BY THE DEPARTMENT, OR THE WASD INSPECTOR.
- 3. THE ASSEMBLY SHALL BE INSTALLED IN AN ACCESSIBLE LOCATION, APPROVED BY THE DEPARTMENT AND THE WASD INSPECTOR.
- 4 ADJUSTABLE PIPE SADDLE SUPPORT (GRINNELL FIG. 264, OR EQUAL) SIZED TO FIT CURVATURE OF DOUBLE DETECTOR CHECK VALVE ASSEMBLY, WITH GALVANIZED STEEL PIPE AND FLOOR FLANGE.ATTACH FLOOR FLANGE TO CONCRETE SLAB WITH GALVANIZED EXPANSION BOLTS.
- 5 . THE DEPARTMENT SHALL HAVE UNRESTRICTED AND CONTINUOUS ACCESS TO THE BACKFLOW PREVENTION ASSEMBLY.
- 6 PIPING 2" AND SMALLER SHALL BE SCHEDULE 40 GALVANIZED STEEL PIPE WITH GALVANIZED MALLEABLE IRON THREADED FITTINGS, PIPING 2-I/2"AND LARGER SHALL BE DUCTILE IRON PIPE WITH FLANGED FITTINGS. ALL PIPING SHALL BE IN ACCORDANCE WITH WASD CONSTRUCTION SPECIFICATIONS FOR DONATION WATER MAINS. PVC PIPING NOT ACCEPTED BY WASD.
- 7 . ALL EXPOSED METALLIC THREADS SHALL BE PAINTED WITH BITUMASTIC PAINT.
- 8 . ALL OUTLETS SHALL BE PLUGGED WITH BRASS PLUGS.
- 9 . ALL ABOVE GROUND PIPING AND EQUIPMENT, EXCEPT FOR BRASS AND STAINLESS STEEL PORTIONS, SHALL BE FINISHED WITH BLUE ENAMEL PAINT (KOP-COAT 0508 LEAD-FREE), IN ACCORDANCE WITH DEPARTMENT STANDARDS.

	·			GUARD POST DETAIL	WS4.5 CROSS REF.	SPEC. REF.
MIAMI- DADE WATER & SEWER DEPARTMENT	APPROVED 01/04/99	REVISED	STANDAF REDUCED PRE BACKFLOW P FOR WATER - NOT	SSURE ZONE REVENTER SERVICÈ	W	S 8 o _f 4

A.A.A.







BACKFLOW PREVENTER LONGITUDINAL SECTION

TYPICAL SHRUB CHOICES:

1,-JAPANESE BOXWOOD (BUXUS MICROPHYLLA JAPONICA).

- 2.-ENGLISH BOXWOOD (BUXUS SEMPERVIRENS).
- 3.-JAPANESE PRIVET (LIGUSTROM JAPONICUM):
- 4.-SILVER BERRY (ELAEAGNUS DUNGENS).
- 5.-WAX MYRTLE (MYRICA CERIFERA).
- 6.-SILVER BUTTONWOOD (CONOCARPUS ERECTUS SERICEUS).
- 7.-GREEN BUTTONWOOD
- 8.-CAMELLIA HEDGE


NOTE:

SCALE: N.T.S.

1. IF DOMESTIC BACKFLOW PREVENTER AND FIRE SERVICE ARE GOING TO BE USED.
TOGETHER, THE LANDSCAPE SHALL BE PROVIDED TO SCREEN BOTH DEVICES.

2. LANDSCAPING IS REQUIRED AS PER CHAPTER 32, SECTION 32–157(d) OF THE MIAMI-DADE COUNTY CODE.

MIAMI — DADE WATER & SEWER AUTH. DEPT.



STANDARD DETAIL

TYPICAL LANDSCAPE DETAIL FOR DOMESTIC WATER SERVICE LINES AND FIRE SERVICES WS 4.18 SHEET 4 OF 4